

CENTRAL BANK OF INDIA					
PRICE BID for Air Conditioning Work AT Mithakhali Branch					
1	SPECIFICATIONS FOR AIR CONDITIONING MACHINE				
	Item	Nos.	Unit	Rate (Rs.) Excluding GST	Amount (Rs.)
1.1	Supply of ceiling mounted 4 way non inverter cassette AC of 4.0 ton capacity copper condenser and minimum 3 star rating. The unit shall include indoor & outdoor units, cordless remote, drain pump, fan with multi speed motor, media filter, and compressor with refrigerant all complete. Including maintenance/ service till defect liability period and onsite warranty (one year)	2	No.		
1.2	Supplying, Installation, testing & Commissioning of 3 Star Rated 2.0 TR Single Split unit all copper condenser split AC system of approved make, including indoor & outdoor units, copper tubes & drain pipes (10 ft along with machine) all complete as per drg, detail & instruction of Architect. Including maintenance/ service till defect liability period and onsite warranty (one year)	1	No.		
1.3	Supplying, Installation, testing & Commissioning of 3 Star Rated 1.5 TR Single Split unit all copper condenser split AC system of approved make, including indoor & outdoor units, copper tubes & drain pipes (10 ft along with machine) all complete as per drg, detail & instruction of Architect. Including maintenance/ service till defect liability period and onsite warranty (one year)	2	No.		
2.0	LOW SIDE AIR CONDITIONING WORK				
2.1	Installation of 4tr. Cassette AC mentioned above with all necessary materials and manufacturer specifications all complete.	2	Nos.		
2.2	Supplying, Installation, testing & Commissioning of Copper refrigerant piping suitable for 4 ton cassette AC with all required material and insulation. Alu. foil membrane shall be applied to provide resistance against breakdown due to UV radiation for exposed portion of the rubber insulation. This item is also including providing and fixing of power cable from indoor to outdoor. It shall be in total clamping manner above false ceiling. It shall not be placed over the false ceiling nor shall it be fixed with false ceiling members. From the structural ceiling it should hanged with suitable adjustable ring type hanger supports etc. or shall be fixed on wall / beam etc.	200	rft		
2.3	Supplying, Installation, testing & Commissioning of Copper refrigerant piping suitable for 2 and 1.5	550	rft		

	ton cassette AC with all required material and insulation. Alu. foil membrane shall be applied to provide resistance against breakdown due to UV radiation for exposed portion of the rubber insulation. This item is also including providing and fixing of power cable from indoor to outdoor. It shall be in total clamping manner above false ceiling. It shall not be placed over the false ceiling nor shall it be fixed with false ceiling members. From the structural ceiling it should hanged with suitable adjustable ring type hanger supports etc. or shall be fixed on wall / beam etc.				
2.4	Providing & Fixing of insulated PVC drain lines with all necessary fitting accessories, Elbows, Tees, wall Sleeves etc. for various units in clamping manner above false ceiling & in concealed manner below false ceiling level. From the structural ceiling it should hanged using self-threaded rods or shall be fixed on wall /beam etc. with clamps. It shall not be placed over the false ceiling nor shall it be fixed with false ceiling members. It shall be laid required gradient for easy disposal of the drain water & testing shall be done before filling the zaries. The drain line shall not be laid in the floor. All drain pipes should be UPVC Heavy Duty of suitable size as recommended by manufacturing company and it should be connected to the nearest rain water pipeline/ as per the site condition. Necessary opening on the wall / glass may be done finishing with cement plaster / new glass / sealant etc.	200	rft		
2.5	Core Cutting of wall	1	Job		
2.6	Supplying & Fixing suitable MS Stand for 1.5/2.0 ton AC outdoor	3	No.		
2.7	Supplying & Fixing suitable MS Stand for 4 ton AC outdoor	2	No.		
				Total=	
Total in word Rs.					

Notes:-

1. Place this financial bid in envelope no.2
2. In case of any discrepancy between unit price and total price of an item, the unit price will prevail. Similarly, in case of error in the sum of various items, the correct sum will be calculated by the addition of total prices of each item.
3. Total Rate/Amount should be **EXCLUDING GST**. GST will be payable extra as per applicable rules. The quoted rate will be inclusive of all other taxes & charges labour charges, cost of transportation, caring, wastages, lifting for all leads, etc.
4. Guarantee Period: On Site comprehensive Guarantee period for the air-conditioner units and other materials supplied should be 12 months from the date of virtual completion and for poor workmanship, poor performance, and in case of deficiencies are found during guarantee period, the same shall be rectified or replaced free of cost by the Contractors at their own cost and risk.

5. Service: Vendor has to provide mandatory on-site services to installed Air conditioners units within Guarantee period of one year, failing which Bank will deduct expenditures incurred by Bank from AC from retention money.

Place:

Date:

SIGNATURE OF CONTRACTOR WITH SEAL