

REQUEST FOR QUOTATION

FOR

ELECTRICAL REPAIRING/ WIRING & REPLACEMENT OF ELECTRICAL FITTINGS/EQUIPMENTS WORK AT ZONAL OFFICE BUILDING, KOLKATA

(PART-I & II)

To,
Assitant General Manager
Zonal Office- Kolkata
Central Bank Of India

Estimated Cost Of Project: 10.00 Lacs

From,

NAME OF BIDDER: _____

ADDRESS : _____

DATE:

Seal and Signature of Contrator

PART-I

Notice of Invitation of Bid

OFFICE MEMORANDUM /2021-22 DATED 01.02.2022

Sealed Quotations are invited on urgent basis from Empaneled and GST Registered Vendors of Central Bank Of India Zonal Office, Kolkata for the Electrical Repairing/ Wiring/ Replacement of Electrical Fittings and Equipment's work at our Zonal office Building, Central Bank of India located at 33-NS Road, Kolkata- 700001 for which the documents can be collected from Zonal Office, Central Bank Of India 6th floor Located at 33 NS Road, Kolkata- 700001 or can be downloaded from our Bank's website www.centralbankofindia.co.in from 03.02.2022

Starting date of Tender	03.02.2022 from Bank's website www.centralbankofindia.co.in . The Tender document can also be collected from our Zonal Office, Central Bank Of India 6 th floor Located at 33 NS Road, Kolkata- 700001
Time and Last date of Submission	On and before 3:00 pm on 11.02.2022 to Assistant General Manager- Zonal Office, Kolkata.
Opening of quotation	At 4:00 pm 14.02.2022 (May be changed subject to prior information to Participants).
Scope of work	As per PART II
Validity of the Quotation	15 Calendar Days.
Labor charges, Transportation and Lifting of Material	The amount quoted should include Labor charges, cost of transportation, Carriage, wastages and lifting for all leads, work, Cass etc.
Eligibility criteria	Only Empanel Vendors of Central Bank Of India, Zonal Office Kolkata/ GST Registered Vendor and those who fulfill eligibility criteria can Participate.
Tender Fee	500/- Non Refundable in favor of "CENTRAL BANK OF INDIA" (Bankers Cheque/DD)
EMD	25,000 /- (Rs. Twenty Five thousand only)
Terms of Payment	Interim Payment at 5.00 Lacs of work duly Certified by Bank's Civil Engineer.
Retention Money	5% Retention money shall be retained for a period of 6 (Six Months) Defect Liability period.
Details of IEM	Dr.
Tender	Envelope-I: Shall contain all the covering letter/ Pages duly signed and sealed. Envelope- II Shall contains the Price Bid, duly filled in the Price Bid Tender Document provided.

Note: The bank is not bound to accept the lowest quotation & reserves the right to accept or reject any or all the quotations without assigning any reason whatever.

Seal and Signature of Contrator

GENERAL TERMS & CONDITIONS: -

1. Contractor is requested to inspect the site/premises, prior to submission of tender/quotation to acquaint itself with the site conditions.
2. Items to be carried out are listed in the attached Schedule of quantities. The Bank reserves the right to add/omit any items/partly or fully, without giving any reason.
3. The Contractor shall at his own expenses rectify the unsatisfactory works within 7 days. In case the Contractor fails to do so, Bank reserves the right to carry out the work through any other agency/agencies and such expenditure will be recovered from the Contractor in the due course of time.
4. All soil, filth, rubbish, debris, electric waste and other objectionable materials shall be at once carted away/ removed by the Contractor out of the premises/site as per local authority's rules in force, if any, at his own cost and expenditure. In absence of above the Bank may do so at the Contractor's risk and cost.
5. The Bank doesn't bind itself to accept the lowest or any tender and reserves itself the right to accept or reject any or all the tenders, without assigning any reasons for doing so.
6. The tenderers are requested to sign the tender form, and the schedule of quantities on all pages, otherwise the same shall be rejected.
7. No extras shall be paid for any minor alterations made in design/specifications, while work is in progress. The rate for any new/extra items shall be settled by the Bank, after getting necessary rate analysis from the Contractor.
8. No advance shall be paid. However interim payment shall be made after certification of work of amounting of Rs. 5.00 Lacs duly certified by Project Engineer.
9. Rates quoted in the tender/quotation should be valid for at least 90 days from the last date of receiving the tenders.
10. 5% of total billed amount of work will be retained with the Bank till the completion of defects liability period of 6 (Six) months and shall be released after Six months, if there are no defects/complaints about the work done and a certificate to that effect is given by the competent authority of the Bank.
15. The last date of submission of tender is 11.02.2022 p.m. on 3 p.m. addressed to Assistant General Manager- Zonal Office Kolkata.
16. Enclosure of Copy of Empanelment /GST Registration and copies of all eligibility proof is Mandatory.

ELEIGIBILITY CRITERIA:

- 1) GST Number.
- 2) PAN Number.
- 3) Trade License.
- 4) Electric Contractor License and License under Contract Labour (Regulation and Abolition Act, 1970).
- 5) Empanel Certificate of Central Bank of India or any other Bank/PSU's/CPWD/ Govt Sector.
- 6) Minimum 10 Years of Experience.
- 7) Last three year Audit Balance Sheet or Last three year IT return.
- 8) Completion Certificate minimum two works above 5.00 Lacs in last five years of similar nature.
- 9) Work in Hands.
- 10) Avg. turnover of Last three years will be 15.00 Lacs and above.

Execution of Work:

- The work should commence within the period specified on i.e. 7 days from the date of the receipt of work Order or the date that may be indicated in the work order. Accordingly, date of commencement of the work will be reckoned from the day as specified above.
- Time allowed for execution of work, shall be the essence of the contract. However the tenderer shall plan the execution of the said work and it needs to be carried out Without disturbing the running of the office or as per the client's instructions strictly within the schedule Time
- If the tenderer commits default in commencing the work, as required by the work order and found that the date stipulated cannot be adhered to, Central Bank of India-Zonal Office- Kolkata shall be entitled without prejudice to any other rights or remedies available and/or may terminate / rescind the contract.
- If the tenderer fails to commence the work within the specified days i.e. 7 days as from the date of Receipt of intimation for commencement of the work and / or the contractor fails to show progress in execution of work and Central Bank of India-Zonal Office- Kolkata, feels the work cannot be completed within the stipulated time, Central Bank of India-Zonal Office Kolkata will have the right to terminate the contract by giving three days' notice to the contractor.
- All the materials and workmanship shall be of the kind described in the schedule of quantities/ specifications and in accordance with relevant BIS codes and as per directions of the Project Engineer-in-charge.
- The tenderer shall not at any time do, cause or permit any nuisance on the site/ do anything which shall cause unnecessary disturbances or inconvenience to the occupants / visitors at site or near the site of work.
- The quantities indicated in the bill of quantities are approximate and the quantities may vary as per the site conditions / requirements. The rate quoted should be firm for the deviated quantities of work also.
- The tenderer's workers will not be allowed to stay at the work site. However any deviation of the same is at the discretion of the Bank

PART 2

TECHNICAL SPECIFICATIONS

List of Approved Materials:

1. The followings are a non-exhaustive list of preferred brand of materials to be used. In case of any items for which no brand is mentioned, then the Contractor may, after obtaining approval from Bank / Architect, use material of a popular brand readily available in the market. The Bank / Architect shall have the right to refuse to accept any items used by the Contractor without their consent, at any time of the execution of work or after completion and the Contractor is liable to replace the items with an approved one without any financial obligation on the part of the Bank.

Electrical Works:

SL NO	MATERIALS / ITEMS	SPECIFICATIONS / BRAND
1	Electrical Panel	Legrand / ABB / Siemens or equivalent
2	MCCB / RCCB / MCB	L&T / Legrand / Siemens / MDS / Havells or equivalent
3	Distribution Board	Legrand / L&T / Siemens / MDS or equivalent
4	Switch Fuse Unit	Havells / Standard / Siemens or equivalent
5	Voltmeter / Ammeter	AE / L&T or equivalent
6	On-load Changeover Switch	Havel's / Samrat / L&T or equivalent
7	PVC Conduit	Plaza / Prestoplast / Precision / AKG or equivalent
8	Armoured Cable	Gloster / CCI / Polycab or equivalent
9	Copper Cables / Wire: Electrical	Finolex / Havel's or equivalent
10	Modular Switch / Socket	MK Wrapround / Anchor Roma / Legrand or equivalent
11	Piano-type Switch / Socket	Anchor / Preeti or equivalent
12	Starter Switch & Plug-top	Northwest / Crabtree / MK or equivalent
13	Category 6 Cable	D-Link / Lucent or equivalent
14	Telephone Wire	Polycab / Finolex or equivalent
15	Light Fixture	Philips or equivalent
16	Lamps	Philips or equivalent
17	Ceiling Fan	Crompton Greaves / Bajaj or equivalent
18	Wall-mounted Fan	Crompton Greaves or equivalent
19	Exhaust Fan	Crompton Greaves or equivalent

Seal and Signature of Contrator

CENTRAL BANK OF INDIA, ZONAL OFFICE KOLKATA BUILDING
Tender for Electrification Work.

Sr. No.	Description of Item	Qty	Unit	Rate	Amount
1	POINTING WIRING FOR TOILET BLOCK				
	Distribution wiring in 2 x 22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheated copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit'FR'(Precision make), with 1x22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheated copper wire for ECC ,to light/fan points with Modular type switch(Brand approved by EIC) fixed on Modular GI switch board with top cover plate and 2 nos suitable size "PH & N" copper bar & earthing attachment fixed on wall incl. mending good damages to original finish. Average run	150.00	NOS		
2	POINTING WIRING FOR STAIRCASE BLOCK				
	Distribution wiring in 2 x 22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheated copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit'FR'(Precision make)[for ceiling portion only]and in 19 mm bore,3 mm thick polythene pipe[for horizontal & vertical run embedded in wall] with 1x22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheated copper wire for ECC, to light points with Modular type switch (Brand approved by EIC) fixed on Modular GI switch board complete with 2 nos suitable size "Ph & N" copper bar with top cover plate making earthing attachment fixed on wall incl. mending good damages to original finish.[only PVC rigid Conduit on ceiling and remaining portion concealed] Average run	150.00	NOS		
3	Supply & laying circuit line in existing wiring including cleaning of wiring with damages necessary connection for 2 x 2.5 + 1 x 1.5 sqmm copper wire	1200.00	RM		

Seal and Signature of Contrator

4	Dressing and refixing with necessary short link MS Chair & MCB channel.				
	a) 8 way TPN DB	25.00	NOS		
	b) 12 way TPN DB	20.00	NOS		
	c) 8 way SPN DB	20.00	NOS		
5	Supplying & fixing 415V,25A FP MCB in SS Enclosure WITH IP-20/30 protection, powder coated provision for housing four pole MCB on flat iron frame incl. painting , connection & provision for earthing attachment	20.00	NOS		
6	Repairing of existing Exhaust Fan	15.00	Nos.		
7	Tube lights (LED)	70.00	Nos.		
8	Supply & fixing of existing raceway cover changed by suitable size of raceway cover including Enamel painting on the MS cover.	300.00	Mtr		
9	Supplying and fixing 240/415 V MCB of breaking capacity 10KA & C characteristics on Din rail of existing DBs and necessary connection	25.00	NOS		
	a) 63A TPN Isolator	20.00	NOS		
	b) 100 A FP MCB Isolator	500.00	NOS		
	c) 10/16 A SP MCB	125.00	NOS		
	d) 32 A HRC Fuse	25.00	NOS		
	c) RYB LED Indicator lamp	25.00	Nos.		
	Total				

Amount in Words: _____ + GST

CONTRACTOR'S SIGNATURE & SEAL

Seal and Signature of Contrator

Project Engineer: Nilesh Haldhar
Sr. Manager Civil Engineer
Zonal Office Kolkata

Seal and Signature of Contrator