

BOQ FOR PROPOSED INTERIOR WORK FOR CENTRAL BANK OF INDIA Mylapore Branch

FURNISHING WORK

Sl. No	Description of Item	Qty.	Per Unit	Rate	Amount (Rs)
A	COUNTERS				
A01	OFFICER TABLE WITH SIDE TABLE				
*	Table Size :- 4'-6" X 2'-0"				
*	Side Table Size :- 2'-6" X 1'-6"				
	Providing & Fixing officer table & side table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303, IS710 & IS1659 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table including side table shall be 2'-6". Depth of the table shall be 3'-0" & side table shall be 1'-6". The counter top to have a 12mmthk PLAIN glass partition of 12" height, positioned 6" from Customer side of the Table Top. The top of glass to be slightly curved and also to have cut-out for transactions with Garware Film (Ice Dot) (Basic Cost Of Film Rs.36/- PerSFT) fixed (at one inch from cut-out edge) as a border to semicircular cut-out and curved top. The table shall have one drawer for key board at the corner of the table & side table. The 1'-6" wide side-unit to have two drawers and one shutter below the drawers at the right side of the bigger table. The front apron shall be made of Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303, IS710 & IS1659 fmg of three cash drawers of equal depth. Front of drawers 18mm thick plywood and 12/6mm thick plywood for side/bottom. Each drawer should have vertical partitions for keeping the currency not Side table to have 2 Drawers at the top and 1 openable shelf at the bottom. All the exposed surfaces of the table & side table shall be finished in 1.00mm thick approved color laminate for vertical surfaces and 1.5mm thk approved color laminate for horizontal surfaces. Foot Rest made Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303, IS710 & IS1659 framework tapered box finish with Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Architect. All exposed surfaces including working TOP of counter shall have decorative laminate. All exposed surfaces shall have 1.00mm thk approved color laminate in two shades for vertical surfaces & approved color 1.5mm thick laminate for horizontal surfaces. The internal surfaces shall have FRENCH polish including approved Single Lock for Drawer Units, approved Stainless Steel Brush Finish Handles, approved Brass Powder Coated Wire Manager, Twin Type Telescopic Drawer Channels, Footrest with Rubber Matting etc. complete as per instructions of Architect. The rates shall be inclusive of making of the opening for the Electrical / ComputerWires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots.	5	Nos		
A02	SUBSTAFF COUNTER (Plain)				
*	Table Size :- 4'-0" X 2'-6"				
	Providing & Fixing clerical counter made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303, IS710 & IS1659 framework for top, sides, apron, drawer box, CPU stand, sides, top, shelves, shutters. 12mm thk Commercial ply (Phenol bonded, water proof (BWP)) IS303, IS710 & IS1659 for drawer sides, & 6mm thk Marine ply for drawer bottom with necessary 2" X 2", 2" X 1 1/2" SalWood supports. All exposed surfaces including working TOP of counter shall have decorative laminate. All exposed surfaces shall have 1.00mm thk approved color laminate in two shades for vertical surfaces & approved color 1.5mm thick laminate for horizontal surfaces. The internal surfaces shall have FRENCH polish including Footrest with Rubber Matting etc. complete as per instructions of Architect. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots.	2	Nos		
A03	CHIEF MANAGER TABLE WITH SIDE TABLE				
*	Table Size :- 6'-0" X 3'-0"				
*	Side Table Size :- 3'-6" X 1'-6"				
	Providing & Fixing Chief Manager table & side table made of Phenol bonded, water proof (BWP) 18mm thk Commercial ply IS303, IS710 & IS1659 framework & necessary 2" X 2" & 2" X 1 1/2" SalWood supports & bedding patti as required. The height of the table including side table shall be 2'-6". Depth of the table shall be 3'-0" & side table shall be 1'-6". The counter top to have a 12mmthk PLAIN glass partition of 12" height, positioned 6" from Customer side of the Table Top. The top of glass to be slightly curved and also to have cut-out for transactions with Garware Film (Ice Dot) (Basic Cost Of Film Rs.36/- PerSFT) fixed (at one inch from cut-out edge) as a border to semicircular cut-out and curved top. The table shall have one drawer for key board at the corner of the table & side table. The 1'-6" wide side-unit to have two drawers and one shutter below the drawers at the right side of the bigger table. The front apron shall be made of Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303, IS710 & ISing of three cash drawers of equal depth. Front of drawers 18mm thick plywood and 12/6mm thick plywood for side/bottom. Each drawer should have vertical partitions for keeping the currency notes. Th Side table to have 2 Drawers at the top and 1 openable shelf at the bottom. All the exposed surfaces of the table & side table shall be finished in 1.00mm thick approved color laminate for vertical surfaces and 1.5mm thk approved color laminate for horizontal surfaces. Foot Rest made Phenol bonded, water proof (BWP) 12mm thk Commercial ply IS303, IS710 & IS1659 framework tapered box finish with Rubber Matting, Brass Powder Coated Wire Manager, Twin Telescopic Drawer Fittings, Locks, CPU metal stand with casters, necessary teak wood round 2" Moulding etc. complete as per instruction of the Architect. All exposed surfaces including working TOP of counter shall have decorative laminate. All exposed surfaces shall have 1.00mm thk approved color laminate in two shades for vertical surfaces & approved color 1.5mm thick laminate for horizontal surfaces. The internal surfaces shall have FRENCH polish including approved Single Lock for Drawer Units, approved Stainless Steel Brush Finish Handles, approved Brass Powder Coated Wire Manager, Twin Type Telescopic Drawer Channels, Footrest with Rubber Matting etc. complete as per instructions of Architect. The rates shall be inclusive of making of the opening for the Electrical / ComputerWires / Switches & A.C. Pipes etc. complete. All exposed portion, beading, moulding shall be of 1st Quality Teak Wood only without knots.	1	NO.		
B	PARTITIONS				
B01	FULL HEIGHT PARTITION (Both Side Laminate Finish)				
	Providing & Erecting in position approx 8'-0" (or) 12'-0" height or as per the actual sitecondition partitions to be made out of 2" X 2" C.P.T.Wood frame work 1'-6" /2'-0" c/c both ways with antitermite chemicals covered with 9mm thk Marine plywith proper joinery with 3/4" X 3/4" MOULDINGS at both end finish with approved color FRENCH polish etc. complete. The frame work shall be coated with antitermite treatments or chemicals. Teak wood members of partitions shall be rigidly fixed to the existing Ceiling, Floors, Beams, Doors & the Side Walls, whichever is applicable & as directed. 9mm X 9mm GROOVES shall be provided as directed. All the exposed surfaces of the partition including grooves as required / directed on the site, upto false ceiling height shall be finish with 1.00mm thick laminate in 2 or 3 shades. 4" Teak wood SKIRTING with FRENCH finish shall be provided at bottom level. The partition to have Hollow Flush Doors as per the thickness of the partition teakwood thick wooden sections for locks, fittings etc. with 4" X 2" c.p.l. wood frame around with teak wood bracers 2" X 2" at 2'-0" at 2" X 2" c/c both ways with 6mm thick Commercial ply (MR grade) IS303 covering on both sides finish with 1.00mm thk laminate of approved shade make along with approved Brass Hinges, Powder Coated Brass Stopper & ISI Floor Spring of DORMA make, approved make Brass 8 Lever Locks and Brush Finish Stainless Steel Handles, Cylindrical Lockable Handles etc. complete as per detail drawing & instructions of the Architect. The necessary openings in the partitions shall be provided for A.C. Grill, Electrical Conduits, Electrical Switches, Light Fixtures, Painting, A.C. Opening, Running Display, Speaker, Fire Detectors, Electric Fixtures, Wall Paintings, Planter Boxes, Mirror, Fixtures as per requirements or instructions. NOTE :- Height of the partitions upto soffit of false ceiling shall be considered for payment but not above it. However the alternate & corner vertical members of the partitions shall continue up to the R.C.C. Ceiling, Beams to the R.C.C. Ceiling, Beams. (UPS room)	220	SFT		
B02	Low HEIGHT PARTITION				
	Do as above ITEM NO.B01 (Both Side Laminate Finish), but partition upto 4' height with top of Wood MOULDINGS finish with FRENCH polish etc. complete as per instructions of the Architect. Glass to have etching paper sticker as per Bank design.	40	SFT		
C	DOOR				
C01	BOTH SIDE LAMINATE DOOR WITH DOOR FRAME (Electrical Room)				
	Providing & fixing both side laminate door including door frame made out of 4" X2 1/2" C.P.T.Wood frame fixed as per required position including shutters made out of 4" X 1 1/2" teak wood frame all round with 6" X 1 1/2" panel at 3'-0" in height including 2" X 1 1/2" brass at 1'-6" c/c both ways. 6mm thk Commercial ply (MR grade) IS303 covering on both sides finish with approved color 1.00mm thk laminate including frame work of approved shade / make along with PUNIT or SHALIMAR make Heavy Brass Hinges, Brush Finish Stainless Steel Handles as per approved, 9" Height 2 Nos. Brass Powder Coated Tower Bolts & Brass Aldrof including Hooks & each shutters Border, Ladies, Gents, Pantry Lettering or in picturised manner etc. complete as per the instructions of Architect.	1	Nos		
C02	BOTH SIDE LAMINATE DOOR WITH DOOR FRAME with 12mm Thk PARTIAL GLASS				

Sl. No	Description of Item	Qty.	Per Unit	Rate	Amount (Rs)
	Providing and Fixing 12mm thick PLAIN partial glass (4' x 2') door made out of 4" X 2" salWood frame for top, bottom & sides with 1" X 1" salWood Mouldings of approved design to fixed the glass & finish with FRENCH polish etc. complete. The 12mm thick PLAIN glass with Garware Film (Ice Dot) (Basic Cost Rs.36/-Per SFT) or "V" cut engraving fixed in the frame work along with Brush FinishStainless Steel 1" Dia 2'-0" Height approved design Handles with 8 Lever Locks, Pull & Push Plate, DORMA make Heavy Duty Floor Spring, Brass Stopper etc. complete as per the detail drawing & instructions of the Architect. Glass to have etching paper sticker as per Bank design.	Quote rate only	Nos		
D	STORAGE				
D01	LOW HEIGHT STORAGE - Laminate Finish				
	Providing & Erecting low height storage 1'-6" deep. The top, sides, drawers, slidingshutters / folding shutters and shelves shall be made out of 18mm thk Commercial ply (MR grade) IS303 with C.P.T.Wood frame work. All exposed surfaces finished with 1.00mm thick laminate of approved shade from outside & FRENCHpolish of similar shade from inside including Brass fittings and fixtures, Stainless Steel Brush Finish Handles, 6" Tower Bolts, Box Hinges, Shelves at 1'-6" c/c with drawer below as shown in the detail drawing & instructions of the Architect.	80	SFT		
E	Cash Cabin Providing and erecting in position of cash cabin along with side and front partition with following specifications:- Basic Workstation —Overall size 1500mm long, 750 mm wide and 750 mm high. Top, verticals, front apron, shall be made of 18 mm thick plywood. Workstation also includes a customer top of size 1500 mm x 300 mm at 1100 mm high from finished floor level. Customer top & front shall be of 18mm thick ply fixed on working top and side partitions/wall with necessary hardware complete. All exposed surface to be covered with suitable teak wood mouldings. The table shall also consist of CPU stand made up 19mm ply. Footrest shall be teakwood section of 4" x 1 1/2" size. The table shall also consist of CPU stand made up 19mm ply and 4" x 1 1/2" teakwood footrest. Providing and fixing of PVC made key board tray with telescopic channels or laminated board on Z shaped powder coated runner with PVC soundless rollers. Cash drawer unit of approx. overall size 400mm wide, 500 mm deep and 680 mm high comprising of three cash drawers of equal depth. Front of drawers 18mm thick plywood and 12/6mm thick plywood for side/bottom. Each drawer should have vertical partitions for keeping the currency notes. This item includes all necessary hardware and central locking systems. All exposed surfaces are finished with 6mm thick TW lipping patti. Finishing: All exposed surface of work station including drawer facia customer top, shall be finished with 1mm thick laminate of approved colour along with 4" high skirting (in two shades) at bottom. Inner portion of table and drawers shall be painted with 2-3 coats of synthetic enamel paint along with putty upto Bank's satisfaction. All wooden surface/Teak wood mouldings shall be well polished with melamine polish. Cash Cabin Side partition - Providing and fixing both side laminated partly glazed partition of size 7' length and 5'6" high with specifications mentioned above. Side partition shall contain opening (9"x6") for voucher passing and tray at 900mm height from finished floor level. The sill level of glass shall be from 1100 mm from finished floor level. The work also includes providing and fixing of door both side laminated with night latch and other necessary hardware complete. Cash Cabin front partition —cash cabin shall have 12 mm clear float glass fixed on side partitions/wall paneling. Glass shall contain necessary cutouts for operation. Glass edges shall have machine polished finish. Fixing arrangements of glass shall be with SS D brackets.	1	Nos		
F	FALSE CEILING				
F1	Gypsum Board False Ceiling				
	Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling, through strap hangers 25 X 0.5 mm (MF 8) at 122 cm centres connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion raw plugs 1/2" dia and 17/16" long with additional channels (MF6A) for light fittings, air conditioners Ducts, vertical drops (upto 9") , offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc., complete.	1350	sqft		
F2	GRID Ceiling:-				
	with fissured mineral fibre board tile 600 x 600 x 12 mm thick (Armstrong or approved equivalent) over the suspended grid system with hot dipped pre-coated GI angle sections 24 x 24 x 0.9 mm size on walls / partitions T Sections 24 x 38 x 0.7 mm size in bottom directions to form 600 x 600 grid. Necessary cut outs for lighting fixtures, air conditioner, air conditioning grills etc. to be provided	250	sqft		
G	Providing & fixing FORM SLIP Counter & cheque drop box . The counter shall made cut of 19mm Comm. Block Board all the expose surface shall finish with 1 mm approved laminate. All the partition shall finish with laminate 1.0 mm thick. The counter shall have 3'0" dia 12mm thick Beveled Glass top. The counter shall rest on casters of flyrail heavy duty complete in all respects.	1	Nos		
H	Channel Gate : Supply and fixing of channel gate for main entry in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	1	Nos		
I	Collapsible shutter: Providing and fixing of shutter leaf type for entry in office area from Customer area , Made in 18 mm Commercial board and finished in laminate 1 mm complete with hinges and hardware	1	Nos		
	INTERNAL PAINTING. (FOR WALLS & CEILING)				
	Providing and applying washable oil-bound distemper of Approved brand and of approved shade firstly removing old paint with scratching using stiff wire / fiber brush, sand paper, fine steel wool then removing all loose and powdery residue, any fungus and algae thorough brushing, cleaning, making surface imperfections such as holes, dents, small visible cracks by filling using mixture and then after surface preparations, then applying one coat of approved primer, then providing and applying two coats of washable oil bound distemper of approved colour, shade. Complete as per the direction of Consulting Engineer / in-charge.	2200	Sqft		
	Total				

GST 18%
Total