

BOQ FOR PROPOSED AC WORK FOR CENTRAL BANK OF INDIA NEW PREMISES FOR Nungambakkam Branch

AIRCONDITIONING WORK

Sl.No	Description Of Work	Qty	Unit	Rate	Amount (Rs)
A	BANKING HALL/ BRANCH MANAGER CABIN				
1	Supply & installation of 1.5TR capacity high wall split air-conditioner (5 star rated) including 4mts length copper and drain piping and 5KVA voltage stabilizer, installation of outdoor units including stand, civil works complete.	1	1 No		
1	Supply & installation of 2.0TR capacity high wall split air-conditioner (5 star rated) including 4mts length copper and drain piping and 5KVA voltage stabilizer, installation of outdoor units including stand, civil works complete.	5	1 No		
2	Power cable outdoor to indoor	40	1Mtr		
3	Supply & installation of additional 3/4" copper piping and drain piping for the split air conditioners including all civil works complete	20	1Mtr		
4	Supply & installation of pair of MS (Mild Steel) stand for outdoor unit, as per standard design available in the market	10	1 set		
	TOTAL FOR AIR CONDITIONING WORK				

GST 28%

Total