

To
The Manager,
Central Bank of India,
Sowcarpet Branch,
Chennai.

Sub: BOQ for Interior Work

S.No	Description	Qty	Unit	Rate	Amount
1	PARTLY GLAZED PARTITION				
	Manager Server cabin partitions to be done using 50mmx25mm Aluminium frame 1.5 mm thk frame , fixed with 6mm plywood on both side and 1mm laminate sheet (approved colour) from bottom @ 3'0" and upto ceiling.The middle portion fixed 6mm tk glass with etching design & bank logo in glass for 4'0" height.fixed with teak wood beading work.All exposed wooden portion to be in melamine polish finish.Door to be done in the same manner and fixed with door closure, 6" SS handle , lock and all other accessories.	400	sft		
2	NON GLAZED PARTITION				
	Non glazed partition for upto ceiling ht & Strong room partition @ 8'6" ht to be done using 50mmx25mm Aluminium frame 1.5 mm thk , fixed with 6mm plywood and both side 1mm laminated sheet finish (approved colour). Door (flush door) size of 3'0"x7'0" to be done in same manner with view glass, door closure, stopper, handle, locks etc.,	200	sft		
3	CASH CABIN PARTITION				

	Cash cabin partition @7'0" ht. to be done using 50mmx25mm Aluminium frame 1.5 mm thk fixed with 12mm thick glass (to be strictly followed) in front side and fixed with 6mm plywood for both sides and 1mm laminated sheet (approved colour) in 3'0" ht., and balance height with aluminium deco grill , all around with teak wood designed beading work all wooden frames in melamine polish finish. The door to be done in the same manner and to be provided with door closures, godrej night latch etc. (Including front pillar).Customer transaction opening of 6" x6" with door locking provision and voice gap of 2" width slit gap to be provided at 4'6" ht from the ffl.	210	sft		
4	Wall Panelling:				
	Aluminum section of size 2"x1" (grid 2'0"x2'0") frame work and covered with 8mm commercial plywood (one side fixing) finished in lamination. The paneling area given below the false ceiling level. Cost includes for aluminum frame to be extended and fitted up of roof ceiling.	400	Sft		
5	Storages:				
	Providing and fixing of 19 mm thk ply for Top. Sides, front shutters finished with for 1mm thk laminate . For all exposed external surface with necessary lipping at front Inside of the storage to be enamel painted. The rates includes godrej multipurpose lock. 4"S.S handles, hinges etc. are as per in the drawing.	50	Sft		
6	GYPBOARD FALSE CEILING				
	Providing and fixing in position M / F suspended false ceiling to details per drg. No. of Job No. with GI frame work and 12.5 mm tapered type gyp board panels to form grids of 45.7 x 122 cm as per manufacturers specification including provision for stepped shaped ceiling for light through comprising.				
	Frame work of intermediate channels (M.F.T.) at 122 cm centre along one direction M/F ceiling section MF5 at 45.7 cm centres along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling, all to detail as per drg.				

	The intermediate channels suspended from ceiling, through strap hangers 25 x 0.5 mm (MF 8) at 122 cm centre connected to soffit cleats P534 (27 x 37 x 25 x 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with necessary bolts and nuts etc. all connected with additional perimeter channels (MF 6A) for openings for light fixtures, AC ducts, vertical drops, offsets etc. wherever necessary all to detail and as per direction.				
	12.5 mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to form grids of 45.7 cm x 122 cm varied along wall ends etc. including Architectural boxing, design and painting the underside of gyp board with 2 coats of plastic emulsion paint of approved colour over a coat primer etc. complete.	410	Sft		
7	GRID FALSE CEILING				
	Providing and fixing in true horizontal level false ceiling as per the std drawing grid of 15 mm of approved make, using hot dipped galvanized steel section exposed surface chemically cleaned capping prefinished in baked polyester paint wall angle of size 3000 x 19 x 19mm used in the periphery of the ceiling fixed to the wall partition RC column band walls with the help of screws at 600mm C/C.				
	Main runner of size 3000 x 15 x 32 mm suspended at a 1200mm C/C. by using 2mm / 3mm dia GI wire hanger securely fixed to the structural soffit of RC slab by using 6mm anchor fastner at every 1200mm, (max) and 1200mm long cross tee of size 15 x 32 mm to be interlocked between in main runner at 600mm C/C (max) to form a grid of 1200 x 600mm.				
	600mm long cross tee of size 15 x 32 mm fixed in between 1200 mm long cross tee for forming a grid of 600 x 600 mm. Finally laying 15 mm THICK PRIMA FINE FISSURED MICROLOOK EDGE. Fire rating of 60 minutes as per BS 476/23 of 1987, Noise reduction co-efficient (NRC) of 0.55, light Reflectance of > 84%, sound attenuation of 34 db, Thermal conductivity K - 0.052-0.057 W/m ⁰ K, weight of 3.53 kg/m ² and Humidity Resistance of RH - 99%.	1350	Sft		

8	Notice board				
	Providing & fixing of Soft Board on the customer lobby made of jolly board with a fabric of B/R 250/- per metre. The design and the entire work has to be done as per the instructions of the Architect at the time of Execution .Size(4'0" x 3'0")x2	24	Sft		
9	Applying two coats of interior grade emulsion paint of approved colour to internal walls and ceiling including labour charges, cost and conveyance of material etc complete.	2500	Sft		
10	Chairs:				
	Supplying the followings types chairs with premium. Quality mesh back, backrest, contact support, V-type adjustable arms of PU, Moulded of foam seat with push back mechanism, pneumatic gas lift height adjustments, synchro tilting-multilock, 5 pronged nylon base with twin wheel castors. The seat shall be with approved brand fabric of basic cost Rs.250/-per metre. The sample chair should be got approved from the Architect/Bank before supply. The rate includes of transportations, all necessary taxes etc.,				
	Medium Back	2	No		
11	Providing and fixing Rollor blinds for all windows colour and materials selection by the Architect ,Rates including materials cost and labour charges etc.complete.	281	Sft		
12	Labour for Cleaning work in partitions,Glass,Tables etc	1	LS		
	TOTAL				0.00