

To
The Manager,
Central Bank of India,
Sowcarpet Branch,
Chennai.

Sub: BOQ for Air Conditioning Work

S.No	Description	Qty	Unit	Rate	Amount
1	Supply install ation testing and commissioning (SITC) of CASSETTE type split airconditioning unit complete as under				
	Indoor unit comprising cooling coil evaporator fan with motor filters insulated drain pan etc controis/ cutouts/ relays etc mounted inside a powder coated sheet metal cabinet of 2 mm thick duly treated for corrosion protection Capacity 3 TR supply				
	3.0 TR-	4	Nos		
2	ANCILLARY WORKS;				
	Supply and Laying of copper Pipes With rubber insulations rubber white cements wall concealing works,etc.,				
	3.0 TR- 3 for	25	Met		
3	Supply and laying of PVC Blue pipes for water drain from the indoor units with necessary wall concealing works, putty works, etc.,	50	Met		
	TOTAL				0.00