

To
The Manager,
Central Bank of India,
Sowcarpet Branch,
Chennai.

Sub: BOQ for Electrical Work

S.No	Description	Qty	Unit	Rate	Amount
	WIRING				
1	Light/Fan point wiring with 3 of 1.5 sqmm Flame PVC insulated copper conductor to be laid in 2mm suitable PVC conduit with Bend,Couplings, etc.. And fixing with PVC clamps screws etc.All conduits to be laid above false ceiling/partition/concealed in the wall 6A Modular type Switch (MK /ROMA) With Suitable Modular Plate and metal Box.				
	a) One light Controlled by One Switch	34	Pts		
	b) Two Lights Controlled by one Switch	5	Pts		
	c) 6A Switch box Sockets in the switch board itself	10	Pts		
	d) Exhaust Fan points	1	Pts		
	e) Ceiling fan point with regulator	2	Pts		
	f)Wall Mounting Fan (6a Socket with 6a Switch)	12	Pts		
2	Supply & Wiring with Flame Retardant Insulated PVC copper wire as per grade IS 994 for Circuits,Computer point,Power points within 2mm thk PVC conduits with necessary accessories and with proper clamps and to be concealed below the false ceiling It Comprises as follows;-				
	a) 3Runs of 2.5Sqmm copper wire in PVC conduit for circuit mains	250	Mtr		
	b) 3Runs of 2.5Sqmm copper wire in PVC conduit for Power points	200	Mtr		
	c) 3Runs of 2.5Sqmm copper wire in PVC conduit for computer points (alternate ups wiring)	275	Mtr		
	d) 2Runs of 4Sqmm copper wire+2.5Sqmm copper wire in PVC conduit for AC wiring	30	Mtr		
	e) 2Runs of 6Sqmm copper wire+2.5Sqmm copper wire in PVC conduit	35	Mtr		

	f) 4Runs of 6Sqmm copper wire+2.5Sqmm copper wire in PVC conduit	200	Mtr		
	Light Fixtures				
3	Supplying and fixing of LED2'0"x2'0" light fixture with all necessary fixing accessories, arrangements and etc.The size of the fixture asper the manufacturers standards and specifications. Unit-nos. Cost include all necessary accessories like chains, tools, hardwares, lead, lift, wastages, loading, unloadingcharges, transportandetc. (PHILIPS LED fullglow make of" RCI40 B LED31S-6500 PSEODWH"220-240V50HZ	28	Set		
4	Supply & Fixing &Commisioning of Wall Mountable fan with necessary Hardwares etc, (Crompton)	12	Set		
5	Supplying and fixing 6W Speaker	6	Set		
6	Supplying and laying Speaker wiring	150	Mtr		
	TOTAL				0.00