

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

Sr.	Item	Unit	Qty.	Rate (Rs.) Excluding GST	Amount(Rs.) Excluding GST
1	Shifting repair of existing furniture-

				
1.1	Shifting, repairing of existing modular tables from old premises to new premises. This item includes cutting, fitting of tables as per layout.(Sides will be paid extra)	Nos.	8		
1.2	Shifting, repairing of existing backside/side storage from old premises to new premises. This item includes cutting, fitting of storage as per layout.	Sq.ft	45		
1.3	Un-installation, Shifting, re-installation of existing Cash cabin/table modular partition from old premises to new premises with inside painting. This item includes complete re-installation of partitions as per layout.	Sq.ft	400		
1.4	Shifting, repairing of existing cheque writing table unit from old premises to new premises with inside painting. This item includes cutting, fitting of storage as per layout.	Nos.	1		
1.5	Providing and fixing of one side support to modular table made up of 18mm ply with one side laminate other side enamel paint. Including cutting, fitting complete.	Sq.ft	50		
1.6	Extra for 20''sliding channel pair for work station drawer.(Set = Pair of 2 channels)	SET	1		
1.7	Extra for 16''sliding channel pair for side storage.(Set = Pair of 2 channels)	SET	1		
			Total of 1(Rs.)		
2	Procurement new of furniture and renovation items

				
2.1	P/F Solid Wooden/ Partly Glazed Partitions (BM cubicle, Cash cabin, partition wall) Basic frame work: 2'' x 1.5'' Salwood/ aluminium sections at maximum 600 mm horizontal & vertical Spacing as per site conditions. Wooden/ aluminum members of partitions shall be rigidly fixed to the Ceiling, Floors, Beams, Doors & the Side Walls, whichever is applicable. The frame work shall be coated with anti-termite treatments or chemicals. Skin Membrane: Single layered 6 mm thick MR grade plywood on each face. Finishing: Both side finished with 1 mm thick laminate sheet of same or combination shades as per instruction with 4'' high skirting at top & bottom of Bank's pattern (Blue & Red). Glass- 8mm for solid, 12mm for low height partition Cash cabin front partition – toughened 12mm glass	Sq.ft	250		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

	start from 1'3" to 6". The open edges are to be blocked by teak wood bead of required size and design. All provisions to be made for all electrical, networking boxes onto partition framework at required heights/levels with necessary additional supports as directed.				
2.2	Grid False Ceiling- Providing and fixing of false ceilings at all heights of 600 mm X 600 mm X 16 mm Armstrong 15mm exposed/Silhouette grid system. The framework compromise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjuster and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 X 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm X 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200mm cross tees.	Sq.ft	500		
2.3	Gypsum Board False Ceiling: Providing and fixing Gypsum Board False Ceiling with 12mm thick Gypsum board and GI framing comprising of ceiling channel 80mm x 26mm x 0.5mm @ every 457 mm centre, intermediate channel 45mm x 15mm x 0.8mm @ every 1200 mm centre, perimeter channel 20mm x 28mm x 30mm x 0.5mm all along wall/partition, ceiling angle 25mm x 10mm x 0.5 mm and other required fasteners/hardware like, soffit cleats, dash fasteners, nuts, clips, screws etc. The work includes taping and jointing, applying primer, two or more coats of emulsion paint of approved shade / make, making cut-out for light fixtures, etc. The Final coat shall be done with foam roller, and no brush marks should be visible.	Sq.ft	600		
2.4	Toughened Glass partition with one Main Door: - Providing and fixing of 12 mm thick toughened glass partition and one main door of approved make with all SS patch fittings complete. Door item to include lock, pair of 300 mm long D handles and other necessary hardware of Stainless Steel of make all complete and excluding floor spring and pivot.	Sq.ft	50		
2.5	Toughened Glass Door: - Providing and fixing of 12 mm thick toughened glass door approved make with all SS patch fittings complete. Door item to pair of 300 mm long D handles and other necessary hardware of Stainless Steel of make all complete and excluding floor spring and pivot.	Sq.ft	21		
2.6	Providing and fixing of floor spring and pivot set for main door.(One floor Spring + pivot set = 1 set)	SET	1		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

2.7	Wooden paneling: Fabricating and fixing wall/column paneling to consist of 37.5mm x 50mm treated salwood framework or Aluminum Sections at spacing not exceeding 600mm bothways (horizontal and vertical). Paneling framework to be secured to wall surface/column surface. Paneling framework to be clad on one side with 6 mm thick MR grade ply finished with 1.0mm thk laminate including border / skirting of 100mm high & 1.5 mm x 1.5 mm groove at border/ skirting level	Sq.ft	150		
2.7.1	Wooden Paneling patta (Above back side storage, decorative vertical patta with gap for LED strip on wall etc.-) Providing and fixing of paneling patta 1-1.5 feet high of 12/18mm MR Grade ply or as specified with one side laminate of single or multiple shades.(Measurement= widths+ Sides)	Sq.ft	120		
2.8	ACP CLADDING: Design, Supply, Fabrication and installation / Fixing of Aluminium Composite Panels of approved make for external cladding and canopy cladding in combination of solid / Metallic colours, including all necessary frame work and complete weather sealing. The composite panel should consist of 3 mm LDPE sandwiched between 2 skins of 0.5mm thick Aluminium sheet making a total panel thickness of 4 mm. The supporting framework shall be made to suit the grid requirement at site out of extruded section 38x38x3mm aluminium angle section or 50x25x1.6mm tube section running vertically or horizontally fixed to building structure through M.S clamps prefixed to masonry with suitable anchor fastener or screws as required after aligning the framework for level and lines. The ACP panel cut to size and bent at edges to form a tray to be fixed to aluminium grid tubes cleats, angles etc with metal screws. All hardware will be corrosion resistant. The gaps will be sealed using weather sealant like Dow Corning 789 or any other approved brand. Note: the external surface shall be well protected with self-adhesive peel off mask.	Sq.ft	190		
2.9	Branding Strip (4.5''-5'' wide below false ceiling):- Providing and fixing wall strip over the existing wall madeup of 12 mm thick ply of approve make finish with 1.0 mm thick mica of approve make & shade. Open edges shall neatly finished.	RFT	150		
2.10	3 feet high backside storage- Providing and fixing of 3 feet high and 16'' to 18'' deep backside storage cabinet with 19mm MR grade ply and 6mm backply. All external surfaces is laminated with 1mm approved laminate and 6mm lipping patti with polish. Internal surface to be painted. Storage shall contain one shelve and 2 door shutters. This item also includes all necessary hardware, handle and locks.	Sq.ft.	85		
2.11	2.5 feet high side storage - Providing and fixing of 2.5 feet high and 16'' to 18'' deep side storage	Sqft.	25		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

	cabinet with 19mm MR grade ply and 6mm backply. All external surfaces is laminated with 1mm approved laminate and 6mm lipping patti with polish. Internal surface to be painted. Side storage shall contain 2 drawer unit and 1 storage units containing one shelve and 2 door shutters. This item also includes all necessary hardware, handle and locks.				
2.12	Providing and fixing of table 2.5 feet high and 2.5-3 feet wide table with 18mm MR grade ply containing table top, sides, drawer facia, CPU stand. Front modesty, drawer sides shall be 12mm ply. The drawers to run on telescopic drawer channels. Drawer units to have two smaller and one bigger drawers with locking arrangement (Godrej or equivalent) the rate to include all hardware such as drawer channels, SS handles, hinges, locks etc. Foot-rest 3''x2'' 2nd class saalwood member to be fixed to table. Oust side surface finished with 1mm approved laminate and inner side painted with enamel paint upto Bank's satisfaction. Rate will inclusive of providing plastic shoes and fixing 19x5mm suitable polished wood beading to all exposed edges etc. Skirting it to be done with approved color laminates. The item also includes a tray for key board running on telescopic channel.	RFT	4		
2.13	Doors/Wicket doors:- Providing and fixing of 35mm solid core flush door with both side laminated with approved laminate and all necessary hardware and handle, lock. For wicket door 18mm thick MR Ply and both side laminate door with necessary hardware.	Sqft	60		
2.14	12mm glass top with cloth – Providing and fixing of 12 mm glass top with cloth. This item is including cutting of wire manager holes etc.	Sqft	90		
2.15	Electrical Panel Cabinet with door: Providing and fixing Electric Panel Cover box as per drawing made of 18 mm thick Ply finished with 1.0 mm thick laminate in front side and paint inside all Complete with hardware fittings. There shall be provision for air ventilation.	Sqft.	25		
2.16	Notice Board: Providing and fixing notice board of 4'-0"X2'-6" size in ply board of 6mm fixed on a frame of 50 mm x 25 mm well-seasoned wood polished and top fixed with bead. 12mm thick. Soft board cladded with fabric of matching color and shade complete with all fixtures necessary as required	Nos.	1		
2.17	Providing and fixing of door closer.	Nos.	3		
			Total of 2=		
3	Supply, Installation, Testing, Commission of Electrical Fixtures.				

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

	Item	Unit	Qty.	Rate(Rs.) Excluding GST	Amount(Rs.) Excluding GST
	Supplying, installation with hanging support, testing and commissioning of following light fixtures with electronic Ballasts, Tubes, lamps, all fixing materials including connecting wires etc. all complete as per the directions of Engineer-in-charge. 				
3.1	36 watt, 2800 lumens square 2'X 2' LED light with necessary fixtures.	Nos.	13		
3.2	14-15 w ,Minimum 850 lumens LED ROUND DOWN LIGHTER Diameter 110-165mm.	Nos.	8		
3.3	4feet long 20w Light batten plain fitting with acrylic cover complete	Nos.	12		
3.4	400 mm sweep Wall bracket fan of approved make complete.	Nos.	1		
35	15w LED bulb	Nos.	2		
3.6	ding dong bell	Nos.	1		
3.7	LED Strip light with adapter complete	Mtr	30		
			Total of 3=		
4	Electric wiring and Switches 				
	Item	Unit	Qty.	Rate(Rs.) Excluding GST	Amount(Rs.) Excluding GST
4.1	Main Panels and Distribution Boards

				
a	Removing, transportation of existing main panel and re-installation at new premises including connection, wiring and testing.	Nos.	1		
b	Removing, transportation of existing UPS input/out DB and re-installation at new premises including connection, wiring and testing.	Nos.	1		
c	Removing, transportation of existing UPS SPN DB and re-installation at new premises including connection, wiring and testing.	Nos.	1		
e	Removing, transportation of existing Stabilizer and re-installation at new premises including connection, wiring and testing.	Nos.	7		
f	Distribution Boards:- Supply, Installation, Testing and commissioning of the surface / recess mounting following way TPN MCB three phase distribution board for Light/Power/AC and UPS separately including neutral, earth bars, direct on wall incl. electrical connection ,earthing , making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed including the followings accessories- 				
f1	Light Distribution & Power Distribution Board(8 way TPN single door) Incomer:- 1 No. 63 Amp 100 ma sensitivity RCCB 4 Pole 3 No. 32 Amp DP MCB Outgoing:- 12 nos. 6 /10/16/20 Amp SP MCB	Nos.	1		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

	Set as above				
f2	AC Distribution Board:- (4 way distribution TPN single door) Incomer:- 1 No. 63 Amp TPN MCB Outgoing:- 6 nos. 25Amp DP MCB Set as above	Nos.	1		
g	Supply and fixing of TPN 125 A Switch Fuse Unit (SFU) with HRC fuse in sheet steel enclosure on M.S. angle frame / M.S. legs on wall complete with interconnection, mending good damages to original finish, painting, etc" as required.	Nos.	1		
				Total(Rs)	
4.2	Earthing System

				
a	Providing chemical or dedicated earthing with 600x600x3.15mm copper plate along with 50mm dia.10feet long G.I pipe with other accessories in the earth filled with necessary salt, charcoal, etc. It should be covered with G.I Manhole cover with necessary civil works etc. complete.	Nos.	2		
b	Supply & Laying of 8SWG copper wire from earth station to UPS and lighting MCB DB.	Mtr.	30		
c	25 mm heavy duty PVC conduit.	Mtr.	10		
				Total(Rs.)	
4.3	Cables and cable laying

				
	LT Cables:- Supply & Laying of the following cables in built up trenches, on wall, or in the ground as per the case may be, with proper clamping with necessary fixing materials etc. Installing, testing & commissioning of 1100V grade UG cable with GI wires as per IS 7098/1554

				
a	3.5C X 35 Sq.mm AYFY ALU armored cable (Main)	Mtr.	20		
b	4c X 10 Sq.mm copper armored cable (Main panel to UPS, & AC DB)	Mtr.	25		
c	4c X 16 Sq.mm copper armored cable (ATM)	Mtr.	10		
d	2 x 6 Sq.mm + 1x 2.5 Sq.mm FR PVC coated copper conductors (1.1 KV grade) in pvc rigid pipe/capping-casing on surface of wall duly clamping with necessary fittings and accessories from Main DB to POWER/LIGHT DB. Including all necessary terminals etc complete.	Mtr.	2		
				Total(Rs.)	
4.4	Cable end termination:-

				
a	3.5C X 25 Sq.mm AYFY ALU cable (Main)	Nos.	2		
b	4c X 10 Sq.mm copper cable	Nos.	2		
c	4c X 16 Sq.mm copper cable (ATM)	Nos.	2		
4.5	Internal wiring

			Total(Rs.)	
	Supply of all required materials and wiring to circuits/ submains with following number and sizes of FRLS PVC insulated 1100 volt grade standard copper wire run in suitable PVC conduit pipe of ISI mark with conduit accessories like bend , junction box etc in concealed/surface manner as per site as required and copper wire as earth continuity conductor and complete in all respect including making good to all damages caused, cleaning the site etc complete as required as per site requirement and as directed.

				
a	Providing and fixing of PVC trunking of 50mmx50mm	Mtr	3		
B	2x 2.5 Sq mm + 1x1.5 Sq mm copper wire circuit mains	Mtr	150		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

	for raw power points, lights and glow sign board. (LDB to Switch boards). For 16A power point maximum 2 points in a circuit. For 6 A power point maximum 3 point in a circuit.				
c	2x 2.5Sqmm + 1x1.5 Sq mm copper wire for circuit mains (UPS DB to Computer) Maximum 3 workstations in circuit.	Mtr.	70		
d	2 x 4sqmm + 1x1.5 sq mm copper wire (From AC DB to AC point)	Mtr.	150		
				Total(Rs.)	
4.6	Point Wiring

				
	Point wiring with 1100 V grade 3 nos. single core 1.5 sq.mm PVC insulated flexible FRLS copper conductor cable (IS:694) through suitable size PVC conduit complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall from light & fan switch board to light, fan & 6A socket outlet on the same switch board or separately mounted switch board. The work includes supply and fixing of all materials such as modular type 6A switch for each light and fan point, 6A 2/3 pin socket outlet with switch, 3 plate ceiling rose / angle or batten 				
a	1 light point controlled by one switch	Nos.	18		
b	2 light point controlled by one switch	Nos.	8		
c	Wall fan/Exhaust fan controlled by 6 Amp socket and switch on light switch board	Nos.	8		
d	Call bell point	Nos.	1		
e	Ceiling fan point with modular type regulator and switch.	Nos.	2		
				Total(Rs.)	
4.7	Power Point Outlets

				
a	6A Raw Power Poin (On Board) -Supply, Installation, Testing and commissioning of onboard modular switch board containing 1 no 5pin 6A socket with switch including cover plate, sheet steel box / PVC modular box etc. of approved make on table/wall.	Nos.	10		
b	6A Raw Power Point (shifting) -Removing, Shifting and reconnection of existing 6A Raw power point fixed on table from existing premises to tables on new premises.	Nos.	7		
b	6A Raw Power Point (Special, New) -Supply, Installation, Testing and commissioning of modular switch board containing 1 no 5pin 6A socket with switch including cover plate, sheet steel box / PVC modular box etc. of approved make on table/wall.	Nos.	7		
c	16A Raw Power Point -Supply, fixing, testing and commissioning of modular switch board containing 1 no. 16 A switch & 1 no. six pin 6/16 Amp. Multi Socket with cover plate, sheet steel /PVC modular box etc on surface / concealed manner.	Nos.	2		
d	6A UPS Power Point (shifting) -Removing, Shifting and reconnection of existing 6A UPS power point fixed on table from existing premises to tables on new premises.	Nos.	7		
e	6A UPS Power Point -Supply, fixing, testing and commissioning of 1 no. 6 A switch & 3 no. six pin 6 Amp. Socket with cover plate, PVC modular box etc on surface / concealed manner.	Nos.	7		
f	AC Point - Supply & Installation of modular type AC box (tiny trip type) with 20 Amp. socket & 20A SP MCB	Nos.	7		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under RO Jamnagar.

	complete to be provided near indoor unit.				
g	Timer for Glow sign Board -Supply, installation and testing of timer with contactor controlling the glow sign board with all accessories complete as required as per direction of Engineer incharge. The system will be a part of the panel board.	Nos.	1		
				Total(Rs.)	
4.8	Telephone wiring

				
a	Supply & laying of 0.5mm dia. Tinned Copper 2 pair telephone cable in the prelaidd data cable conduit.	Mtr.	35		
b	Supply & Fixing of RJ 11 Telephone Sockets with PVC modular box and faceplate complete.	Nos.	3		
c	Supply & Installation of 10Pair KRONE Box with Enclosure	Nos.	1		
4.9	Shifting of Electrical Fixtures

			Total(Rs.)	
a	Removing, Shifting and installation of existing wall bracket fan from existing premises to new premises of branch	Nos.	7		
b	Removing, Shifting and installation of existing ceiling fans from old premises to new premises	Nos.	3		
c	Removing, Shifting and installation of existing exhaust fans from old premises to new premises	Nos.	2		
d	Removing, Shifting and installation of existing 2x2 LED lights from old premises to new premises.	Nos.	2		
d	Providing and fixing of Fan hook and rod	Nos.	3		
			Total of 4 (4.1 to 4.9)		
5	Data Cabling Works

				
	Item	Unit	Qty.	Rate(Rs.) Excluding GST	Amount(Rs.) Excluding GST
a	Supply and lying of CAT6 Network cable in the PVC conduit	Mtr.	250		
b	Supply and fixing of RJ45 Network socket with front plate and base box for computer workstations.	Nos.	17		
c	Supply and fixing of 3 feet patch card	Nos.	9		
d	Supply and fixing of 7 feet patch card	Nos.	9		
e	Shifting, Testing, commissioning of router, patch panel, rack, modem, switch etc. from exiting branch to new premises.	LS	1		
			Total(Rs.)		
6	Shifting and Copper Piping of AC

				
	Item	Unit	Qty.	Rate(Rs.) Excluding GST	Amount(Rs.) Excluding GST
8.1	Shifting of AC from old premises to new premises including uninstallation, reinstallation. 				
	Split unit	No.	6		
82	Supplying & Laying extra suitable Copper refrigerant piping with all required material including power cable from indoor to outdoor suitable for 1Tr/1.5 tr /2 tr load/AC.	rft	110		
8.3	Supplying & Laying extra suitable PVC Drain piping with all required material.	rft	50		
8.4	Supplying & Fixing suitable MS Stand for 1.5 tr/2 tr AC outdoor.	No.	6		
			Total(Rs.)		

Commercial Bid (Online Mode) for Furniture, Renovation, Electrical, Data Cabling and AC piping works of Ranjeetnagar Branch under R0 Jamnagar.

Summary of total works-

Sr. no.	Particular	Amount (Rs.) Excluding GST
	Furniture and renovation works-	
1	Repair/shifting/renovation of existing furniture	
2	Procurement of new renovation items	
	Electrical works-	
3	Supply, Installation, Testing, Commission of Electrical Fixtures.	
4	Electric wiring and switches	
5	Data Cabling works	
6	Shifting of existing Air-condition machine and copper piping works	
	Total=	

Above rates and amounts are excluding GST and GST as applicable shall be charged extra.

Seal and signature of Contractor