



निविदा दस्तावेज/RFQ DOCUMENT
(नियम, शर्तें एवं ड्राइंग्स/Terms, Conditions & Drawings)

Request for Quotation (RFQ) for Establishing NRI Desk at B/O (Seven Bungalow, Borivali, Santacruz (West)), Andheri and Juhu Vile Parle (JVPD) Under North Mumbai Regional Office.

(Empaneled Vendors under Works Category Upto Rs .10.00 Lakhs)

विज्ञापन की दिनांक/ Date of Advertisement	12-11-2025
प्रस्तुत करने की अंतिम दिनांक / Last Date of Submission	19-11-2025 by 15:00 Hrs.
खुलने की दिनांक Opening Date	19-11-2025 by 15:30 Hrs
कार्य अवधि/Time Period of Work	कार्य आदेश प्रदान करने की दिनांक से 14 दिन 14 days from award of Work Order
प्रस्तुत किए जाने वाले दस्तावेज/ Documents to be provided	Empaneled Vendors Under Works Category Upto Ra.10.00 Lakhs
बयाना जमा राशि/Earnest Money Deposit	रु./Rs.6000. मात्र (सेन्ट्रल बैंक ऑफ़ इंडिया के पक्ष में मांग ड्राफ्ट जो थाइन पर देय हो/ Rs.6000.00(Rupees Six Thousand Only) DD In favor of Central Bank Of India, Payable at Mumbai.
MSME firms are exempted from EMD/Tender Fees corresponding registration documents to be submitted	
संपर्क व्यक्ति/Contact person name	Mr. Satish Suryavanshi, Manager – Regional Office (NMRO) Mr.Amarnath .V – Architect.
बोलियां जमा करने का स्थान / Place of submission of Bids & opening of bids	Regional Office Address (NMRO) Central Bank of India, North Mumbai Regional Office, 3 rd floor, NCL Building, Plot No. 6 'E' Block, Bandra Kurla Complex, Bandra (East), Mumbai-400051
E-mail id for correspondence	gadmsro@centralbank.bank.in rmmsro@centralbank.co.in archmmzo@centralbank.bank.in

प्रस्तुतकर्ता/SUBMITTED BY:

ठेकेदार का नाम/NAME OF CONTRACTOR :
पता/ADDRESS :
जीएसटी विवरण/GST DETAILS :

NMRO/ BSD/ 2025-26:03

12-11-2025


Reg.:- Request for Quotation (RFQ) for Establishing NRI Desk at B/O (Blank) Under Regional Office (NMRO)

Sealed quotations will be received by the (Central Bank of India, North Mumbai Regional Office, 3rd floor, NCL Building, Plot No. 6 'E'Block, Bandra Kurla Complex, Bandra (East), Mumbai-400051 **up to 3:00 p.m. on (19-11-2025) and will be opened on the same day at 3.30 p.m.** नियम एवं शर्तें/ Terms and conditions:

1. प्रतिस्पर्धात्मक दर प्रस्तुत करने के पूर्व वेंडर साइट का निरीक्षण करें/ The vendor has to inspect the site before offering the competitive quote.
2. क्षेत्रीय कार्यालय द्वारा फायनल भुगतान समय पर एवं संतोषपूर्वक कार्य पूर्ण होने के उपरांत किया जाएगा. सभी भुगतान नेफ्ट के माध्यम से किए जाएंगे / The final payment will be will be made by the Regional Office on satisfactory and timely completion of work. All payments will be made through NEFT.
3. बैंक के पास किसी भी समय बिना कोई कारण बताए अनुबंध रद्द करने/ आंशिक अथवा पूरी तरह परिवर्तित करने का अधिकार सुरक्षित है. यदि कंपनी द्वारा वांछित मानक/मरम्मत/रखरखाव एवं इंस्टालेशन के मानदंड और उल्लिखित समय सारणी का अनुपालन और नहीं किया गया है तो बैंक के पास इंस्टालेशन/रखरखाव आदि के लिए देय राशि से किसी भी राशि तक कटौती/अर्थ दंड लगाने का अधिकार भी सुरक्षित है./ The Bank reserve the right to terminate / modify the contract partly or fully, anytime without assigning any reason whatsoever. The Bank also reserves the right to deduct / forfeit any amount as deemed fit, payable for the installation / maintenance in case the required standards / specification of repairs / maintenance and installations are not kept / maintained and time schedule as laid down is not adhered to by the Company.
4. वेंडर को कार्य पूर्ण होने का प्रमाण पत्र प्रबंधक वास्तुविद अथवा बैंक के किसी प्रतिनिधि से जो कार्य को सुपरवाइज़ कर रहा है द्वारा विधिवत हस्ताक्षरित प्रमाण पत्र लेना होगा/ The vendor is also required to get the work completion certificate duly signed by the Architect or any representative of the Bank supervising the work.
5. प्रभारी अधिकारी के विधिवत रूप से हस्ताक्षरित कार्य पूर्ण होने के प्रमाण पत्र सहित इनवाइस की प्रति (जीएडी) विभाग क्षेत्रीय कार्यालय को कार्यालयीन रिकार्ड के लिए प्रस्तुत की जानी चाहिए/The copy of the invoice along with the work completion certificate duly signed by Officer in charge has to be submitted with the Regional Office (BSD) for the office record.
6. बैंक के पास बिना कोई कारण बताए किसी अथवा सभी निविदा/कोटेशन को स्वीकार अथवा रद्द करने का अधिकार सुरक्षित है/The Bank reserves the right to accept or reject any or all the tenders / quotations, without assigning the any reasons for doing so.

7. निविदा/कोटेशन में दशाई गई दर में सामग्री/मजदूरी/परिवहन इत्यादि शामिल होना चाहिए एवं बैंक इस संबंध में अन्य किसी व्यय के लिए जिम्मेदार नहीं होगा. यह दर निविदा/कोटेशन की प्रस्तुति की दिनांक से 6 माह के लिए वैध होंगी./ The rates quoted in the tender / quotation should include all charges for material, labour, transportation and taxes, etc. and Bank shall not be responsible for any other expenses in this connection. The rates shall be valid for minimum 6 months period from the date of submission of the tender / quotation.
8. निविदकर्ता से अनुरोध है कि वे निविदा फॉर्म पर हस्ताक्षर करें अन्यथा निविदा/कोटेशन रद्द किया जा सकता है/ The tenderer is requested to sign the tender form, otherwise the tender / quotation is likely to be rejected.
9. कोई भी अग्रिम प्रदान नहीं किया जाएगा. बैंक की संतुष्टि के अनुसार कार्य पूर्ण होने पर फायनल इनाइस प्राप्त होने की दिनांक से एक सप्ताह के अंदर भुगतान किया जाएगा/No advance shall be paid. Payment shall be done only on completion of the work to the satisfaction of the Bank with in one week from the receipt of the final invoice.
10. सामग्री को स्टोर करने की जिम्मेदारी वेंडर को अपनी लागत पर करनी होगी/The storing of material shall be the vendor's responsibility at his cost.
11. वेंडर वर्कमेन कंपनसेशन एक्ट, कांटेक्ट लेबर, शॉप एंड एस्टब्लिशमेंट, पॉलिसी ऑफ इंश्योरेंस, फायर इंश्योरेंस सहित सभी लागू लेबर लॉ के अनुपालन के लिए जिम्मेदार होगा. उक्त का दावा किसी भी प्रकार से कभी भी आप इसे बैंक से दावा नहीं किया जा सकेगा/The vendor shall be responsible and liable for compliance of all applicable labour laws including Workmen's Compensation Act, Contract Labour, Shops & Establishment, Policy of Insurance, Fire insurance. At no time shall you claim the above from the Bank.
12. वेंडर को कार्य करते समय इस बात का ख्याल रखना होगा कि परिसर, इलेक्ट्रिकल केबल इत्यादि का नुकसान न हो. यदि कोई नुकसान होता है तो वेंडर को इस आपनी लागत पर ठीक कराना होगा./The vendor shall take care that the work is carried out without causing damage to the premises, electrical cables, etc. Any damage caused shall be rectified by the vendor at his own cost.
13. वेंडर को उसके द्वारा नियुक्त कर्मचारियों की विश्वसनीयता, सद्भाव आचरण एवं ईमानदारी का ध्यान रखना होगा. वेंडर द्वारा अथवा अन्य एजेंसी जानबूझकर अथवा लापरवाही से कार्य किए जाने से होने वाले नुकसान की भरपाई आपको करनी होगी/The vendor shall vouch for safe, bonafide conduct and fidelity of the staff employed by him. Any damages caused willfully or in negligence to the work executed by him or other agencies shall be borne by him.
14. साइट पर कार्य के लिए प्रयुक्त होने वाली सभी सामग्री की निगरानी की जिम्मेदारी वेंडर की होगी/ Watch and ward in respect of all materials / equipment at the site for use in work shall be the vendor's responsibility.
15. रु.6,000.00 मात्र की बयाना राशि सेन्ट्रल बैंक ऑफ इंडिया के पक्ष में आहरित मांग ड्रॉफ्ट जो थाइन पर देय हो के माध्यम से जमा की जानी होगी/Earnest Money Deposit (EMD) of Rs6,000/- (Rupees Six Thousand only) is to be paid through DD favoring Central bank of India, payable at **Mumbai**.

16. कार्य आदेश की प्राप्ति से (02) सप्ताह के भीतर कार्य पूरा करना होगा. इसमें किसी भी प्रकार के विलंब के लिए प्रोजेक्ट की लागत का 1 प्रतिशत प्रति सप्ताह के हिसाब से दंड लगाया जाएगा जो अधिकतम प्रोजेक्ट की लागत के 10 प्रतिशत के अधीन होगा/The work has to be completed within maximum two (02) weeks from getting the confirmed work order. Any delay beyond this period will attract a penalty of 1% of the cost of the project per week subject to maximum 10% of the cost of the project.
17. कार्य की पूर्ण होने की दिनांक से 6 महीना तक की गारंटी होगी. बिल की राशि का 5 प्रतिशत बैंक द्वारा 6 महीना की दोष देयता को पूरा करने के लिए अपने पास रखा जाएगा/The work shall be guaranteed for a period of 6 Month from the date of completion. 5% of the bill shall be retained by Bank till the completion of defect liability period of 6 Months.
18. किसी भी कारण से विलंब से प्राप्त एवं ई मेल/टेलीग्राफिक निविदाओं पर विचार नहीं किया जाएगा/ Tenders received late on account of any reason whatsoever and e-mail / telegraphic tenders will not be entertained.
19. प्रत्येक निविदा के साथ निविदा मांग ड्राफ्ट जो पर देय हो के माध्यम से बयाना जमा राशि संलग्न होना चाहिए. निविदाएं जो निविदा की लागत एवं मांग ड्राफ्ट के माध्यम से बयाना जमा राशि के साथ संलग्न नहीं होंगे उन्हें गैर उत्तरकारी मानकर रद्द किया जाएगा/ EMD by Demand Draft payable at Mumbai must accompany each tender and the tenders not accompanied by the Cost of Tender and EMD by Demand Draft are liable to be rejected as NON-RESPONSIVE.
20. बैंक न्यूनतम निविदा को स्वीकार करने के लिए बाध्य नहीं है एवं बैंक के पास किसी भी अथवा सभी निविदाओं को स्वीकार अथवा रद्द करने का अधिकार सुरक्षित है/ The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all tenders.
21. कोट की गई दर में बिना बढ़ोत्तरी के कोई बदलाव नहीं होगा एवं 6 माह तक बाध्य रहेंगी/The price quoted shall be firm and binding without any escalation whatsoever for six months.
22. (A) तकनीकी एवं दर सारणी अनुबंध I में दर्शाई गई है/ the technical specification & rate schedule is placed at: Annexure-I

भवदीय/Yours faithfully,

()
Regional Head

ल ऑफ क्वांटिटि के लिए प्राक्कथन/PREAMBLE TO THE BILL OF QUANTITIES

प्रस्तावित कार्यालय परिसर में प्रस्तावित कार्य निविदा के आवरण पृष्ठ (पृष्ठ नं. निविदा के आवरण पृष्ठ (पृष्ठ संख्या 1) में उल्लेखानुसार करना होगा. प्रस्तावित कार्य की गुणवत्ता में सर्वश्रेष्ठ कारीगरी होना चाहिए। ठेकेदार को यह सुनिश्चित करना चाहिए कि प्रोजेक्ट के लिए सामग्री की सूची में उल्लिखित सामग्री श्रेष्ठ गुणवत्ता की हो.

The work proposed to be carried out at the proposed Office premises as mentioned on the cover page (page no.1) of the tender The quality of work proposed should have **the best** workmanship. The contractor should ensure that only the first quality materials mentioned in the list of material is purchased for the project.

1. कार्य इस तरह से किया जाए कि स्वरूप में कोई गड़बड़ न हो.

The work should be carried out in such a way that the structure is not disturbed.

2. निविदा प्रस्तुत करने से पहले विनिर्देशन में किसी भी अंतर/विसंगति को को प्रभारी इंजीनियर के साथ स्पष्ट किया जाना चाहिए। प्रभारी इंजीनियर को कार्य के दौरान मूल अवधारणा के अनुरूप एक उचित सीमा तक विनिर्देश को संशोधित करने की स्वतंत्रता होगी; निविदाकर्ता को ऐसा कार्य बिना अतिरिक्त लागत के करना होगा.

Any difference / discrepancies in the specification should be clarified with the Engineer in charge before submitting the tender. The Engineer in charge will have the liberty to modify the specification to a reasonable limit to suit the basic concept during the course of work; the tenderer should carry out such work without any extra cost.

3. किसी भी बड़े संशोधन के मामले में ऐसी वस्तुओं को अतिरिक्त मद के रूप में माना जाएगा. ऐसी मदों का भुगतान का इंजीनियरिंग दर / बाजार दर विश्लेषण के आधार पर किया जाएगा. सामग्री और श्रम की कुल लागत का 15% निविदाकर्ता के लाभ के रूप में माना जाएगा.

In case of any major modification such items will be considered as extra items. Payment for such items will be paid based on the Engineering rate / Market rate analysis. 15% of the total cost of material and labour will be considered as tenderer's profit.

4. ठेकेदार को सुचारु कार्य प्रवाह के लिए साइट पर नियुक्त अन्य ठेकेदार के साथ समन्वय करना होगा.

The contractor should co-ordinate with the other contractors employed at the site for smooth flow of work.

NOTE:

The building is occupied by the Bank. The work needs to be carried out as per the instruction of the Bank time schedule. Further, the work needs to be carried in phase wise. The Contractor should prevent the external glazing and the flooring with plastic sheets and P.O.P. sheet respectively.

1. The contractor should obtain necessary permission from the BMC any Government Authority if required along with the security deposit amount, the security amount will be reimbursed to the contractor.
2. The Contractor needs to clean the site on day-to-day basis.

BILL OF QUANTITIES:

Note:

1. Rates to be quoted by the tenderers in the item rate tender in figures and words shall be accurately filled in, so that there is no discrepancy in the rates written in figure and in words. However, if a discrepancy is found between the rate written in figures and rate written in words then the rate which correspond with the amount worked out by the contractor shall be taken as correct.
2. If the amount of an item is not worked out by the tendered, or it does not correspond with the rate written either figures or in words, then the rate quoted by the tenderer in words shall be taken as correct.
3. Where the rate quoted by the tenderer in figures and in words tally but the amount is not worked out correctly, the rate quoted by the contractor will be taken as correct, not the amount.
4. The work needs to be carried out as per the time schedule instructed by Bank.
5. All other office furniture, office equipment, flooring, false ceiling etc. to be cover with plastic sheet or required packing materials
6. Any damages done by the contractor will be recovered from the contractors.
7. Cleaning to be done on day-to-day basis.
8. Electrician and one supervisor should be posted in working day to avoid any office disturbance and maintain the office smoothly.

(NOTE: The rates should be inclusive of all applicable taxes but exclusive of GST and Only GST as Applicable would be paid as per actuals)



SCHEDULE OF BILL OF QUANTITIES

AS per Attached Annexure

Confirmation of Acceptance of Tender terms and conditions

(To be signed by the bidder and enclosed along with their offer in a separate envelope)

We have studied the terms and conditions of Tender Enquiry including General and Special terms and conditions, the specifications, lay-out drawings, Schedule of Quantities, Commercial terms and conditions, Approved Makes, etc.


We are accepting all terms and conditions of the Tender without any deviation.

Offer with any deviations from the Tender Enquiry are likely to be rejected.

We also understand that the order / s will be placed in the name of principals only and not in the name of their dealer/s. Our quotation is based on the above.

Date: 12/11/2025

**SIGNATURE OF TENDERER
WITH RUBBER STAMP**



DECLARATION

I / We hereby declare that I / We have read and understood the Terms and Conditions of the contract, Specifications, Drawings, Schedule of Quantities etc. and hereby agree to abide by them. In token thereof, I / We have signed below and at the end of the Schedule of Quantities, failing which the tender is liable to be rejected.

I / We understand that our Tender will not be considered if the rates for items are not written both in FIGURES and WORDS.

I / We hereby confirm that only the relevant entries asked for, have been made within the Tender documents issued to us. I / We also confirm that in the event of any entry in this Tender document other than the relevant entry or condition shall make this Tender invalid.

Date : 12/11/2025

**SIGNATURE OF TENDERER
WITH RUBBER STAMP**

Project	Central Bank of India - B/O (BLANK) (BLANK) Regional Office under Mumbai Metropolitan Zonal Office				
Bill of Quantities for Interior ,Electrical and Allied Works					
Sr. No.	Description	Qty	Unit	Rate(Rs.)	Amount (Rs.)
1.00	CORIAN TOP LAMINATE FINISH TABLE	1	No's		0.00
	Providing & fixing Corian top laminate finish table having given size of 1800mm x 900mm with height of 750 mm (as per attached detail drawing) Table having 40 mm Thick. at top made by Corian finish with buffing polishing etc. rest on 18 mm MR grade ply . Top is cantilever then its base supports. Base supports made by 18 mm thick sandwich ply . A Table having two no's of drawers and a shutter for both sides in a pedestal and a key board tray at mid of table. Drawers & Keyboard tray rest on telescopic channels. Shutters & drawers having thickness of 24 mm which are made by 18 mm + 6 mm ply to create conceal grooves as handle. Drawers & keyboard side, Bottom & Back of pedestal are made up of 12 mm thick mr grade Ply Wood. Having 3" high Footrest of 18 mm ply.((1) In elevation of table have a provision of 30mmx30mm PVD patties of suggested shed . and top is rest on that SS studs (is rest on 50 to 100 mm SS stud.)(2)In elevation of table top is partly covered with Corian top and sides have trapezoid vertical support as shown in detail drawing of 18 mm sandwich ply.)All Exposed surfaces covered with 1 mm thick laminate . And internal surfaces covered by 1mm thick laminate. all complete with given no of key board tray, drawers on telescopic channels, locks, stoppers, SS Screws, MS nails, Auto hinges, Cable Manager etc. as per shown in detail drawings & as per instructions of architect/consultant / in charge engineer. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it. Basic rate of core laminate is1800 Rs. per sheet. The table size is taken to be 1800 mm x 900 mm x750mm .(As per drawing)and the side unit is of size 1200 mm/1500 mm x 450 mm.				
2.00	GLASS RAILING	20	Sq.Ft.		
	Providing and fixing 12mm Etched float glass (straight or bent as per shape given in plan) in front with metal clamps/D brackets /S.S. Studs or Wooden supports including cutouts for passing currency as per details The edges of the glass to be polished complete with necessary cutting the holes in shape properly, grinding & polishing. The glass may be fixed in vertical or inclined position as per given drawings.				
3	STORAGE CUPBOARDS	60	Sq.Ft.		0.00
	Providing and Fixing pre lam storage Full height as per details, fabricated out of 19mm pre laminated board. Average depth of storage will be 450mm, shelves also made of 19mm thick BWR ply and finished in laminate. All exposed edges of pre lam shall be covered with PVC banding of required size. Cost of the storages units to be inclusive of pre-approved handles/finger grip, SS self closing Hinges, tower bolts, ball catches, locks and all necessary hardware all complete as per detailed drawing and instruction of Architect/EIC.				
4.00	BANK LOGO BRANDING	4	No's		0.00
	Providing and fixing poster frame fabricated using sheets of 36" x 24 " clear acrylic sheet of 5mm thick and beveled edge well polished to be fixed with 0.75" stainless steel studs				
5.00	Colored Acrylic Sheet LOGO for the Bank ,Back Lit (Overall Size 750 mm x 750 mm)	1	No's		0.00
	Supplying , fabricating and installation of Central Bank's Logo of (Three Col0urs) made of colored acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Colored Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect.				
6.00	Frosting Film/Sun Control Film	150	Sq.Ft.		0.00
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyester film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings up to 0.1 Sq.. area each and nothing shall be paid extra for making such openings.)				
7.00	Painting works	250	Sq.Ft.		0.00
	Providing and applying three coats of pre-approved Plastic emulsion paint to walls,ceiling,partitions etc. . Including surface preperation with two coats of putty ,primer and sanding the same all complete.With the necessary drting periods for each coat. The final finish should be of a uniform and neat finish to the satisfaction of the Architect. Cost to include for all heights and surfaces ,complete in all respect (Low VOC Contain Paint) Make :Asian Paints , ICI,DULUX,Berger .				
8.00	Vinyl Flooring	100	Sq.Ft.		0.00
	Providing and Fixing 2.5 mm thick vinyl flooring as per laying specification of the manufacturer the cost to include wastage and fixing charges size 920mm x 180mm x 2mm Planks. (Basic Cost @ Rs.90/Sq. ft.)				
9.00	Planter Boz with Pot and Plants	20	Sq.ft		0.00
	Bush BOX - GRC Planter - Providing and fixing in position at required location GRC (Glass reinforced Concrete) bush Box planter of height 1500mm ,1500mm length with 500mm as per Architect's Design with all leads and lifts etc. complete in Toto. The rate to include SS finish pot made from SS suggested sizes & Shapes & shade approved by the Architect with Natural /artificial plants .				
10.00	Glazed Partition	200	Sq.ft		0.00
	Providing and fixing fully glazed partitions made of 12mm thick clear toughened glass of approved make fixed in Glass wedge system in the floor and ceiling and with suitable arrangement in false ceiling to provide rigidity to the glazed partition etc. all complete as per drawing, instructions & approval of EIC / Architect. The item included providing and fixing frameless patch fittings Single /Double Door with 12mm thick toughened glass (as per approved design & Name /Logo) with frame less glass fittings and two way floor springs ,Dorset ,OZONE make) .The item included providing and fixing SS.S handles 450mm long on both sides of glass ,locks and fittings as per manufactures specifications .Schedule of patch fittings per panel are as follows 3 MTRS GLASS WEDGE SYSTEM Shoe screw, shoe, flip cap etc. complete as per maufacturer's speciffication.				
11.00	Metallic Grid ceiling	100	Sq.ft		0.00

Project	Central Bank of India - B/O (BLANK) (BLANK) Regional Office under Mumbai Metropolitan Zonal Office				
Bill of Quantities for Interior ,Electrical and Allied Works					
Sr. No.	Description	Qty	Unit	Rate(Rs.)	Amount (Rs.)
	ARMSTRONG CEILINGS – ALY-IN PERFORATED MICROLOOK EDGE METAL TILE WITH ACCOUSTICAL FLEECE WITH XL 15MM GRID: Providing and fixing in Armstrong mineral Fibre Acoustical Suspended Ceiling with ULTIMA (MICRO LOOK) EDGE TILES WITH ARMSTRONG SILHOUTETE EXPOSED GRID.The tiles should have Humidity Resistance (RH) of 95% NRC 0.75, Light reflectance 90%, Thermal Conductivity K=0.57, w/m.K, Sound Attenuation of 37 DB, Colour White, Fire Performance A2-sl.d0 in module size 600 x 600 x19mm with Bio Block coating on the face of the tile, suitable for Green Building Application with Recycled content of 70-80%. The tile shall be laid on Armstrong Silhouette profile grid System with 15mm white flanges incorporating a 6mm central reveal in white/black color. Silhouette, Main runner & Cross Tees to have mitred ends and birds mouth notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 120 grams per M2.Instalation and suspension system as per the OEM Specifications for the product.				
12.00	Light Point wiring				
	Supply & Installation of concealed point wiring using 600v grade 1.5 sqmm copper conductor PVC insulated wires (with proper R,Y,B color code) pulled through heavy gauge PVC conduits laid concealed over false ceiling or in wall chases or on the ceiling in case of an open ceiling including 2.5 sqmm circuit wires from the relevant DB and also including 2.5 sqmm green color copper earth wire and switch plate, switches, etc. as approved by the consultant. (Each circuit shall not feed more than 8 points OR 800 watts as per following configuration.)				
12.1	Primary light points including the cost of 5A switch	5	No's		0.00
12.2	Secondary light points looped from the above point	2	No's		0.00
12.3	5A Plug point on switch board	3	No's		0.00
13.0	Supply & installation of 5/15A Plug Point directly taken from DB etc. including 2 x 2.5 sqmm circuit wires directly taken from the relevant DB and also including 1.5 sqmm green color copper earth wire all laid through PVC conduit with all necessary hardware& accessories, etc. (UPS / Raw Power)	3	No's		0.00
14.0	Supply & Installation of point wiring for UPS or stabilized power plug points on workstations / table for computers using 2 X2.5 Sqmm 1 X 1.5 Sqmm copper conductor PVC FRLS wires pulled through already laid floor raceways and taken upto table top using PVC rigid or flexible conduits run within wooden/metal partitions. Each point consisting of 3 nos of 5A , 2/3 pin sockets & 1 No., 15A Switch , wired together forming one point. (ONLY TWO tables served by one circiut from DB)	3	No's		0.00
15.0	Supply & Installation of point wiring for raw POWER plug points on workstations / table for computers using 2C X2.5 1 X 1.5 Sqmm copper conductor PVC FRLS wire conductor PVC sheathed white color flexible cable pulled through already laid floor raceways and taken upto table top using PVC rigid or flexible conduits run within wooden/metal partitions. Each point consisting of 1 nos of 5A , 2/3 pin sockets & 1 No., 15A Switch , wired together forming one point. (ONLY FOUR tables served by one circiut from DB)	3	No's		0.00
16.0	S & I of 5/a5AMps Socket with 32amps SP MCB plate & box with 15amps top Nr ac Unit.	3	No's		0.00
17.0	Light Fixtures				
17.1	SITC OF PHILIPS / CROMPTON 2 x 2 x 36 Watts LED Light Fixture with accessories such as Chain Link Support on ceiling.	3	No's		0.00
17.2	SITC OF 15/Watts LED down light Fixture.	4	No's		0.00
18.0	Supply,Installation,Testing and commissioning of Wall mounted fans of 400 dia sizes of approved make including 3/5 pin Switch socket in the place as per design	2	No's		0.00
19.0	DATA/Voice				
19.1	Supplying / Installation/ Testing & Commissioning of D LINK make CAT 6 wires from SERVer to each work station	4	Pts		0.00
19.2	Supplying / Installation/ Testing & Commissioning of D LINK make CAT 6 IO with box.	4	No's		0.00
	TOTAL				0.00
	ADD GST @18%				0.00
	GRAND TOTAL				0.00